



PROJECT: **JACKSON COUNTY
SOLID WASTE MANAGEMENT FACILITY TRANSFER STATION**

DATE: **July 9, 2009**

RFP 9182-01 ADDENDUM No. 7

PAGE: 1 OF 1

Plans and Specifications for the referenced project, as prepared by Moreland Altobelli Associates, Inc., are hereby modified in the following particulars:

A. ADDENDA

1. ADDENDUM NO. 5

- a. Modify item B.1.a as indicated below.
- b. Modify item C.4.c. as indicated below.

B. CONTRACT DOCUMENTS MANUAL

1. SECTION 00100 – INSTRUCTIONS TO BIDDERS

- a. Modify paragraph H.1 to read:
“The Bid Proposal will include:
 - a. Completed Bid Proposal Form
 - b. Bid Bond or Certified Check
 - c. Execution of Proposal Form
 - d. Addenda Acknowledgement Form
 - e. Jackson County Vendor Master Form
 - f. Form W-9
 - g. GA Immigration and Security Compliance Act forms and affidavits for Contractor.
 - h. Section 00420 Statement of Contractor Qualifications
 - i. Section 00422 Corporate Certificate
 - j. Section 00480 Non-Collusion Affidavit”

2. SECTION 00800 – SUPPLEMENTAL CONDITIONS

- a. change paragraph 4. PERMITS AND LICENSES to read:
“Permits and fees, including building permit and utility fees, will be paid for by the Owner.”

3. SECTION 02200 EARTHWORK (RE-ISSUED IN ADDENDUM NO. 5)

- 3.08 TEMPORARY EROSION CONTROL: change paragraph to read:
“A. The Owner will provide erosion and sediment control as shown on the plans. All erosion control measures taken shall comply with the Georgia Soil and Water Conservation Committee Standards. The Owner shall periodically inspect and maintain all erosion control devices. The Contractor shall reinstall any erosion control which he damages or must temporarily move for access. Contractor shall coordinate with Owner on the required work area and access prior to Owner's installation of erosion control.”

C. DRAWINGS

1. DRAWING C2.0 - SITE PLAN

- a. add the following note:
“EXISTING RETAINING WALLS ARE INDICATED WITH DASHED LINES. CONTRACTOR SHALL CONSTRUCT THE NEW RETAINING WALL CONNECTING BETWEEN THE NEW TRANSFER BUILDING AND THE EXISTING RETAINING WALL AT THE POINT INDICATED TO BE SAW-CUT ON DRAWING C3.0. SEE DRAWING S1.3 FOR NEW RETAINING WALL”

2. DRAWING C4.0 – SITE GRADING AND DRAINAGE PLAN

a. Add note #17 as follows:

“THE CONTRACTOR WILL INSTALL A CHAIN LINK FENCE WITH OPAQUE STRIPS WOVEN INTO THE FENCE FABRIC AND “W” BEAM GUARDRAIL PER GaDOT STD. NO 4010, 4011 AND 9031 ALONG TOP OF EXISTING AND NEW RETAINING WALL , SEE SHEET C10.2 DETAILS.”

END OF ADDENDUM No. 7

(TOTAL PAGES IN ADDENDUM NO. 7 : 2 PAGES)